QUOTATION

Name of work:-Installation of KWH meter/function meter in AMF panel at DG supply incoming at DG houses in the campus.

S.No.	Description of work	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	1 x 1.5 Sq.mm	60.00	Mtr.		
2	Supplying, installation, testing & commissioning of kWH meter LCD Panel type in AMF panel.	13.00	Nos.		
3	Supplying, installation, testing & commissioning of current transformer of following rating in the AMF panel.				
a)	800/5Amp	12.00	Nos.		
b)	600/5Amp	9.00	Nos.		
c)	500/5Amp	3.00	Nos.		
d)	400/5Amp	9.00	Nos.		
e)	300/5Amp	3.00	Nos.		
f)	240/5Amp	3.00	Nos.		
4	Dismentling damaged switch/DB/KWH meter/ pole fuse box/TPN switches metal helide box with MCB/Pole fuse box and depositing in the section store.	5.00	Nos.		

Total Rs

RAGA VPA क्यां के स्ट्रिक्ट के स्ट्रिक के स