

QUOTATION

Name of work:-Repairing and replacement of faulty meter in residences area , light in 509 Type-V Snehan Child Care Centre , director residence and faulty cable in hall-13 premises as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (in words & Figures)	Amount (in words & Figures)
1	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1kV grade as reqd.				
a	3½ X 95 sq. mm	1.00	Set		
2	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load offollowing poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Single Pole & Neutral	1.00	Nos.		
3	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of fluorescent / HPMV /HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required	1.00	Nos.		
4	Dismantling damaged Switch /DB/KWH meter/pole fuse / loose wire box of any size from site and depositing in store I/c cartage etc. as reqd.	22.00	Nos.		
5	Dismantling and refixing brass compression type gland up to 35 sq. mm. cable	2.00	Nos.		
6	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.	11.00	Nos.		
7	Supplying and drawing of following sizes of FR PVC insulated copper conductor, 3 core round cable of following size in the existing surface/ recessed steel/ PVC conduit as required.				

o.	Description	Qty.	Unit	Rate	Amount
				(in words & Figures)	
a	1.5 Sq.mm	5.00	Mtrs.		
8	Digging cable trench/lifting brick/s and cable for locating fault and refilling the trench, ramming & making good the same as reqd.	48.00	Mtr.		
9	S & F 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a	Triple pole & Neutral	1.00	Nos.		
10	Supplying, fixing, connecting, testing & commissioning single phase electronic kWh meter LCD type of following ratings i/c. sealing the same (sealing material will be supplied by the dept.) etc as reqd.				
a	10-60 A, 230V, 50 Hz	11.00	Nos.		
11	Supply / fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips)				
a	LED bulb 15 W	7.00	Nos.		
12	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	11.00	Nos.		
13	Supplying, fixing, connecting, testing & commissioning direct operated or CT operated 100/5A three phase electronic kWh meter LCD type of following ratings i/c. sealing the same (sealing material will be supplied by the dept.) etc. as reqd.				
a	100/5A , 415V, 50 Hz	1.00	Nos.		
14	Fixing & connecting 1 or 3 phase temporary service connection from supply source to the desired place for lead of 50 mtr and dismantling the same from the source I/c cartage to & fro from store (extension board & cable/wire will be supplied by the dept.)	2.00	Nos.		

No.	Description	Qty.	Unit	Rate (in words & Figures)	Amount
15	Repairing, servicing, testing and commissioning 1 or 3 phase kWh meter I/c sealing the same (sealing material will be supplied by the dept.)	15.00	Nos.		
16	Dismantling & refixing of fitting repairing cleaning of all type of street light fitting on pole/ walls etc. as reqd.	5.00	Nos.		
17	Dismantling of steel conduit pipe of all sizes from surface/recess I/c cutting the wall and making good the same in case of recessed conduit.	60.00	Mtr.		
18	"Disconnecting & dismantling damaged TV box/ loose wire boxes along with all accessories and depositing the same in the store as reqd. and including excavation, sand cushioning, protective covering and refilling the trench etc.	7.00	Nos		
19	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete.				
a	Street Light luminaire 35W CAT no ENDURACITYLITEPLATPLUSL35WLED 757SASYBOPC. Havells make or it's equivalent	1.00	Nos.		
20	Supplying & Laying of one no. XLPE cable copper conductor steel unarmoured cable of size 1 x 35sqmm, grade 1.1kV in following manners.				
a	In existing open duct	4.00	Mtr.		
21	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
a)	35 sq mm	4.00	Nos.		
22	Dismantling & refixing brass compression type cable gland 185 sq.mm to 400 sq.mm. cable.	2.00	Nos.		

Total Rs


 PACHEVISHI & SONS
 सवित्री बाजार, 10/2 (एलेक्ट)
 सावित्री, रा. ...
 I.W.D., ...

