QUOTATION

Name of work:-Provide New electric meter in SIIC Extension -3 near Media Lab Block - B first floor and Tinkering Lab F-1.

S.No.	Description	Qty.	Unit	- Rate	Amount
				(In words & Figures)	
1	Supplying & drawing following sizes of FRLSH PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 4 Sq.mm	9.00	Mtr.		
2	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required				
a)	200 mm X 150 mm X 60 mm deep	2.00	each		
3	Supplying & drawing following sizes of FRLSH PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 16 Sq.mm	10.00	Mtr.		
4	Supplying, installation, testing & commissioning of Single Phase KWH meter 10 - 60A LCD display type .	5.00	Nos.		
5	Supplying, installation, testing & commissioning of 3 Phase 4 Wire KWH meter LCD display type .	2.00	Nos.		
6	Supplying, installation, testing & commissioning of current transformer of following rating in the AMF panel.				
a)	75/5Amp	6.00	Nos.		
7	Supplying & fixing of following size of steel flexible pipe on surface/open duct as required				
a)	25 mm	1.80	Mtr.		

		Qty.	Unit	Rate	Amount
S.No.	Description			(In words & Figures)	
0	Dismantling and refixing of	5.00	Nos.		
	switch/socket/regulator/MCB I/c cleaning connecting commissioning etc as			<i>y</i> -	
	reqd.				

Total Rs.

RAGHVENDRA SINGH लिखानी अभियंता (flo) E.E. (Elect.) चं विश्वित भावकी अस्त्रान, सामपुर I.W.D., L.I.T., Kanpus