

QUOTATION

Name of work: Electrical Maintenance work at south side residence as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	24.00	Nos.		
b)	2 way 5/6 A switch	1.00	Nos.		
c)	15/16 Amp. switch	9.00	Nos.		
d)	3 Pin 5/6 Amp. socket outlet	7.00	Nos.		
e)	6 Pin 15/16 Amp. socket outlet.	7.00	Nos.		
f)	Bell push	1.00	Nos.		
g)	Fan regulator socket type rotary step	11.00	Nos.		
2	Supply & fixing modular blanking plate on exisitng metal boxes but excluding modular plate as req.	5.00	Nos.		
3	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	1 or 2 module	1.00	Nos.		
b)	3 module	4.00	Nos.		
c)	4 module	5.00	Nos.		
d)	6 module	3.00	Nos.		
e)	8 module	1.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
f)	12 module	1.00	Nos.		
4	Supplying and fixing brass batten/ angle holder including connection etc. as required.	24.00	Nos.		
5	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	4.00	Nos.		
6	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	1874.00	Sq.cm		
7	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	7.00	Nos.		
8	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	20.00	Nos.		
9	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	3.00	Nos.		
10	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a)	LED tube light fitting (1 X 18 / 20 Watt. LED) surface mounting luminaires wipro meke	9.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
-------	-------------	------	------	------------------------------	--------

b) 36 watt LED recess mounted luminaires with diffuser suitable for 600 mm X 600 mm modular POP/Gypsem ceiling etc.as reqd. 3.00 Nos.

c) LED tube light fitting (2 X 18 / 20 Watt. LED) surface mounting luminaires wipro make or its equivalent approved make etc as reqd 5.00 Nos.

11 Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.

a) Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd. 30.00 Mtr.

b) On surface with MS clamp 5.00 Mtr,

Total Rs

==



राघवेन्द्र सिंह
RAGHVENDRA SINGH
 अधिष्ठापी अभियंता (वि०) E.E. (Elect.)
 सं० नि० वि०, पा० प्र० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur

