

QUOTATION


Sub. Providing additional power points & internet points in instrument room at Old Sac "A"Block Ground floor.

S. No	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 2.5 sq. mm	100.00	Metre		
b	3 x 4 sq. mm	80.00	Metre		
c	6 x 4 sq. mm	25.00	Metre		
2	Supply and fixing of 32 x 12.5 mm DLP mini- trunking white-system with independent cover etc. as required complete.	20.00	Meter		
3	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	40.00	Meter		
4	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	85 mm flexible cover	40.00	Meter		
b	End cap	16.00	Nos.		
c	Internal angles- adjustable from 80°-100°	8.00	Nos.		
d	external angles- adjustable from 60°-120°	4.00	Nos.		
e	flat junction	3.00	Nos.		
f	flat angles	6.00	Nos.		
g	separation partitions	25.00	Meter		
h	Joints for 85mm width cover	30.00	Nos.		
i	base joints	15.00	Nos.		

5. No	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
5	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Triple pole (40A-63A)	1.00	Nos.		
b	Four Pole (40A-63A)	1.00	Nos.		
6	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
7	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
a	3 Module (100mmX75mm)	2.00	No.		
b	6 Module (200mmX75mm)	5.00	No.		
8	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	26.00	No.		
b	15/16 A switch	26.00	No.		
c	3 pin 5/6 A socket outlet	10.00	No.		
d	6 pin 15/16 A socket outlet	8.00	No.		
9	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3.00	No.		
10	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				

S. No	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
a	3 Module	27.00	No.		
b	6 Module	18.00	No.		
11	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	150.00	Meter		
12	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	5.00	Nos.		
13	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	20.00	Nos.		
14	Supply fixing connecting & commissioning of following rating ISI marked 3 pin Plug top Anchor make as reqd complete.				
a	15 Amp	7.00	Nos.		

Total Rs.


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 इलाहाबादी अभियंता (वि.सं. E.E. (Elect.))
 स.नि.वि.सं. कां.प्रा. अखिल, कानपुर
 I.W.D., I.I.T., KANPUR
