

QUOTATION

Name of work: Providing LAN ports in the rooftop of type -2 Multistoried & Faculty apartment.


S.No.	Description	Qty.	Unit	Rate <small>(In words & Figures)</small>	Amount
1	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a)	6 module	2.00	Nos.		
2	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
3	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	500.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 32 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	On surface with MS clamp	170.00	Mtr.		
5	S&F, connecting and commissioning looping type cable end control box with MS sheet of 16 SWG of size 200 mm x 200 mm x 125 mm having 1 no. 6amp to 32 amp SPMCB 250 volt and 2 nos. brass neutral link square rod 6 way and fixed on 5 mm thick bakelite sheet. Box shall have almirah type hing and panel key type lock front door duly painted with earthing strud etc. complete as required.	2.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
-------	-------------	------	------	------------------------------	--------

6 Providing and fixing following sizes of PVC casing and capping on surface as reqd.

a)	20 x 12 mm	30.00	Mtr.		
b)	25 x 16 mm	30.00	Mtr.		
c)	32x 16 mm	1.00	Mtr.		

Total Rs


 RAGHENDRA SINGH
 अधिसाकी अधिवंता (वि०) E.E. (Elect)
 सं० नि० वि०, मा० प्र०० कल्याण, काणपुर
 I.W.D., I.I.T., Kanpur
