


QUOTATION

Sub Name of the work : Repairing/replacement of defective electrical items in OCL 107B, OCL 205C, Outreach 206, OCL 104D and different labs and offices in academic area on complaint basis.

S.No.	Description of Item	Qty	unit	Rate (In words & figures)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a)	3 x 2.5 sq. mm	15.00	Metre		
b)	3 x 4 sq. mm	80.00	Metre		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a)	5/6 A switch	2.00	Nos.		
b)	15/16 A switch	3.00	Nos.		
c)	3 pin 5/6 A socket outlet	2.00	Nos.		
d)	6 pin 15/16 A socket outlet	3.00	Nos.		
3	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a)	3 Module	1.00	No.		
b)	6 Module	1.00	No.		

S.No.	Description of Item	Qty	unit	Rate (In words & figures)	Amount
4	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a)	Single pole	4.00	Nos.		
5	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	2.00	Nos.		
6	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	5.00	Nos.		
7	Dismantling and refixing of M.S./PVC box of up to 250 x 300 x100 on surface recessed as required. including painting with enamel paint as reqd	1.00	No.		
8	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a)	3 Module	1.00	No.		
b)	6 Module	1.00	No.		
9	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
a)	20 watt ESENTIAL PHILIPS or equivalent Tube inplace of 36/40 W FL tube	1.00	No.		

S.No.	Description of Item	Qty	unit	Rate	Amount
				(In words & figures)	
10	Supply and fixing of following LED light fixture with Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a)	12 watt recess mounting LED light fixture	1.00	No.		
b)	18 watt recess 300 x 300 mm mounting LED light fixture	1.00	No.		
c)	36 watt recess mounting LED light fixture 600 x 600 mm	4.00	Nos.		
11	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete.				
a)	450 mm / 18" sweep	1.00	No.		
Total Rs.					_____


 अविरागी प्रविणता (पिं), ए.एस. (प्लेन.)
 सहायिका, भा.पी. संस्थान, काठपुर
 I.W.D.H.T. KATHUR
