


## QUOTATION

**Subj** Shifting of KESCO 11 Kv HT cable coming in the foot print of Center for Engineering in Medicine Building.

SL No.	DESCRIPTION	QTY	UNIT	RATE (in words & Figures)	AMOUNT
1	Digging trench for taking out cable upto 400 Sq.mm. and refilling , watering ,ramming the same after taking out cable as reqd complete.	150.00	Meter.		
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation and refilling the trench etc as required, but excluding sand cushioning and protective covering.				
a	Above 185 sq. mm and upto 400 sq. mm	20.00	Metre		
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
a	Above 185 sq. mm and upto 400 sq. mm	30.00	Metre		
4	Supply and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 kv grade as required.				
a	120 Sq.mm	4.00	No.		
<b>Total Rs.</b>					_____

  
RAGHVENDRA SINGH  
अभिधी अभिवता (वि०) E.E. (Elect.)  
सुविधि, भाद्रप्रीत संरक्षण, कानपुर  
W.D., I.I.T., Kanpur