

## QUOTATION

Name of work -: Electrical maintenance work at south side residence at RA hostel ,faculty Apartment,old SBRA ,Type -2 Multistorey ,Type-1A, Type -2, New SBRA and outreach building as per enclosed complaints.

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a	1 x 1.5 Sq.mm..	100.00	Mtr.		
b	3 x 1.5 Sq.mm..	14.00	Mtr.		
c	3 x 4 Sq.mm..	12.00	Mtr.		
2	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a	5/6 Amp switch	26.00	Nos.		
b	15/16 Amp. switch	3.00	Nos.		
c	3 Pin 5/6 Amp. socket outlet	8.00	Nos.		
d	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
e	Telephone socket / jack outlet	1.00	Nos.		
f	Call bell push	1.00	Nos.		
3	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a	5/6 Amp switch	8.00	Nos.		
b	15/16 Amp. switch	1.00	Nos.		

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
c	3 Pin 5/6 Amp. socket outlet	2.00	Nos.		
d	6 Pin 15/16 Amp. socket outlet.	1.00	Nos.		
e	Telephone socket outlet	1.00	Nos.		
f	Bell Push	1.00	Nos.		
g	Fan regulator socket type rotary step	4.00	Nos.		
h	Blanking plate	1.00	Nos.		
4	Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a	1 or 2 module	1.00	Nos.		
b	3 module	2.00	Nos.		
c	12 module	1.00	Nos.		
5	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	4.00	Nos.		
6	Supplying and fixing brass batten/ angle holder including connection etc. as required.	18.00	Nos.		
7	Supplying and fixing call bell/ buzzer suitable for ac single phase, 230 volts, complete as required.	1.00	Nos.		
8	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
a	12-way , Double door	1.00	Nos.		
9	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
a	Single Pole	12.00	Nos.		
10	Supplying and fixing following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensitivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
a	40 Amp	1.00	Nos.		
11	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a	Fan regulator socket type rotary/dimmer	2.00	Nos.		
12	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a	20 x 12 mm	16.00	Mtr.		
b	25 x 16 mm	16.00	Mtr.		
13	Supply / fixing , testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free as required complete etc as reqd	2.00	Nos.		
14	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete.				

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
a	LED tube light fitting (1 X 18 / 20 Watt. LED) surface mounting luminaires	3.00	Nos.		
15	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a	1200 mm	4.00	Nos		
16	Supplying and fixing 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	1670.00	Sq.cm		
17	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	6.00	Nos.		
18	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	28.00	Nos.		
19	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	27.00	Nos.		

Total Rs

\_\_\_\_\_

\_\_\_\_\_

Handwritten signature in blue ink.

Handwritten signature in blue ink.

Handwritten signature in blue ink.