QUOTATION

Name of work: Replacement of damaged underground LAN wire in Houses No .2065 & C-6 Old SBRA in the campus .

S.No.	Description	Qty.	Unit	Rate	Amount
	- Th			(In words & Figures)	
	•				
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	170.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	25.00	Mtr.		
b)	25 x 16 mm	30.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	20.00	Mtr.		
b)	In pipe	1.00	Mtr.		
c)	In open duct	1.00	Mtr.		
d)	On surface with MS clamp	1.00	Mtr.		
	W 407 Th				

Total Rs

अधिकारी अभिजना (कि) / हु है (हु हु का) भारत (कि) मां) जी। संस्थान कार्नपुर विकास के विकास कार्नपुर