QUOTATION

Name of work: Providing and Fixing Electrical installation work in newly constructing bathroom at 1st and IInd floor in Visitor's Hostel-2 at IIT Kanpur.

| S.N | Description of item | Qty. | Unit | Rate (In words & Figures) | Amount |
|-----|---|-------|-------|------------------------------|--------|
| 7.5 | 10-10-1-1-1 | | | (In words & Figures) | - 6 |
| 1 | Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required. | | | | |
| 1.1 | Group B | 8.00 | Point | | |
| 2 | Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit/ PVC truncking as required. | | | | |
| 2.1 | 3 x 1.5 sq. mm | 20.00 | Mtr. | | |
| 2.2 | 3 x 4 sq. mm | 15.00 | Mtr. | | |
| 3 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. | | | | |
| 3.1 | 5/6 amp switch | 10.00 | Each | | |
| 3.2 | 2 3 pin 5/6 amp socket outlet | 2.00 | Each | | |
| 3. | 3 15/16 amp switch | 2.00 | Each | | |
| 3. | 4 6 pin 15/16 amp socket outlet | 2.00 | Each | | |
| 4 | Supplying and fixing following size/ modules, GI/PVC box alongwith modular base & cover plate for modular switches in recess etc as required. | | | | |

| | | - 1 | | | | |
|-----|---|-------|------|------------------------------|--------|--|
| | | | i i | D-40 | Amount | |
| .N | Description of item | Qty. | Unit | Rate (In words & Figures) | Amount | |
| 1.1 | 3 Module (100mmX75mm) | 2.00 | Each | | | |
| 1.2 | 8 Module (125mmX125mm) | 2.00 | Each | | | |
| 5 | Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required. | 2.00 | Each | | | |
| 6 | Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required. | 4.00 | Each | | | |
| 7 | Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. | | | | | |
| 7.1 | 25 mm | 8.00 | Mtr. | | | |
| 8 | Supplying and fixing of 200mm sweep Fresh Air fan complete with suitable size louvers and PVC housing with all accessories suitable for use on 230 V, 50 Hz supply in the existing opening, including making good the damage, connection, testing and commissioning etc. as required. | 2.00 | Each | | | |
| 9 | Providing and fixing following sizes of PVC casing and capping on surface as reqd. | | | | | |
| 9.1 | 20 X 12 mm | 10.00 | Mtr. | 3 | | |
| 9.2 | 2 25 X 16 mm | 12.00 | Mtr. | | | |
| 10 | Supplying and fixing wooden board of following sizes on surface/recessed with suitable size of phenolic laminated sheet cover etc. complete as required. | | | | | |
| 10 | .1 100 mm X 100 mm | 3.00 | Each | | | |
| 10 | 0.2 200 mm X 150 mm | 2.00 | Each | | | |

| S.N | Description of item | Qty. | Unit | Rate (In words & Figures) | Amount |
|-----|---|--------|-------|------------------------------|--------|
| 11 | Supplying and fixing 3 mm thick phenolic laminated sheet on existing board with brass screw and cup washer etc. complete as required. | 210.00 | Sq.cm | • | |
| 12 | Supplying and fixing of 10W LED batten luminares on surface mounting complete as required. | 2.00 | Each | | |
| 13 | Supply / fixing , testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free as required complete LED makeHavells or its equivalent make etc as reqd | 4.00 | Each | | |
| | | | | | |
| | Total Rs. | | | | |

First Singh (20)/S.E. (Elect.)

20 100 USENT, ONLY

1. W. D., I.I.T., Kanpur