

**SCHEDULE OF QUANTITY**

**Name of Work: Electrical maintenance work at south side residences as per enclosed complaints.**

Name of the Contractor					
S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
<b>1</b>	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
<b>a)</b>	Group 'A'	1.00	Points		
<b>2</b>	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
<b>a</b>	1 x 1.5 Sq.mm..	20.00	Mtr.		
<b>b</b>	3 x 1.5 Sq.mm..	11.00	Mtr.		
<b>c</b>	3 x 4 Sq.mm..	63.00	Mtr.		
<b>3</b>	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
<b>a</b>	5/6 Amp switch	22.00	Nos.		
<b>b</b>	2 way 5/6 amp switch	1.00	Nos.		
<b>c)</b>	15/16 Amp. switch	13.00	Nos.		
<b>d)</b>	3 Pin 5/6 Amp. socket outlet	20.00	Nos.		
<b>e</b>	6 Pin 15/16 Amp. socket outlet.	11.00	Nos.		
<b>f)</b>	Bell push	5.00	Nos.		
<b>4</b>	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
<b>a)</b>	5/6 Amp switch	38.00	Nos.		
<b>b)</b>	2 way 5/6 A switch	1.00	Nos.		
<b>c)</b>	15/16 Amp. switch	18.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
d)	3 Pin 5/6 Amp. socket outlet	7.00	Nos.		
e)	6 Pin 15/16 Amp. socket outlet.	16.00	Nos.		
f)	Bell push	1.00	Nos.		
g)	Fan regulator socket type rotary step	16.00	Nos.		
5	Supply & fixing modular blanking plate on existing metal boxes but excluding modular plate as req.	6.00	Nos.		
6	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a	3 module	1.00	Nos.		
7	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	1 or 2 module	1.00	Nos.		
b)	3 module	9.00	Nos.		
c)	4 module	4.00	Nos.		
d)	6 module	6.00	Nos.		
e	8 module	1.00	Nos.		
f)	12 module	5.00	Nos.		
8	Supplying and fixing brass batten/ angle holder including connection etc. as required.	18.00	Nos.		
9	Supplying and fixing call bell/ buzzer suitable for single phase,230 V, complete as required.	2.00	Nos.		
10	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
a)	Single Pole	1.00	Nos.		
11	S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensitivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
a	40 Amp	1.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
12	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth metal enclosed plug top along with 20 amps ' C ' series SP, MCB, in the sheet steel enclosure, on surface or in recess, with chained metal cover for the soc	1.00	Nos.		
13	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	100.00	Mtr.		
14	S & F wood board of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a)	100 mm x 100 mm	4.00	Nos.		
b)	175 mm x 100 mm	9.00	Nos.		
c)	200 mm x 150 mm	1.00	Nos.		
d)	200 mm x 250 mm	1.00	Nos.		
15	Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd.	12.00	Nos.		
16	Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	5.00	Nos.		
17	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	3174.00	Sq.cm		
18	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	36.00	Nos.		
19	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	10.00	Nos.		
20	Supply & fixing of 12 W surface mounted light ec.as reqd. make Havells OR equivalent approved make.	2.00	Nos.		
21	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	27.00	Nos.		
22	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a)	Drum light cat No.03 PV / 02 decon make or equivalent.	2.00	Nos.		
b)	Wall bracket Decon make cat. no. 0553 or equivalent.	3.00	Nos.		
c)	Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	2.00	Nos		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
d)	Wall light stylo fitting 14W Havells make or equivalent.	4.00	Nos		
23	Supply, Installation of exhaust fan, 900 rpm 220 volt AC, 50 Hz of following sweep in the existing opening I/c connection, testing, commissioning etc as reqd.				
a	300 mm	3.00	Nos.		
24	Dismantling & refixing of any size fan from normal height				
a	ceiling fan	8.00	Nos.		
25	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	Fan regulator socket type rotary step	3.00	Nos.		
26	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.(make Havells)	2.00	Nos.		
27	S & F 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd. ( legrand)				
a	Double pole	1.00	Nos.		
28	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	2.00	Nos.		
29	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete.				
a	LED tube light fitting (2 X 18 / 20 Watt. LED) surface mounting luminaires wipro make or its equivalent approved make etc as reqd	2.00	Nos.		
30	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a	20 x 12 mm	50.00	Mtr.		
b	25 x 16 mm	1.16	Mtr.		
31	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm <sup>2</sup> ) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	45.30	Mtr.		
b	On surface with MS clamp	1.00	Mtr.		
32	S & F of following LED light fixture with electronic driver. LED lamp , reflector , diffuser , MS body/housing holder etc . Complete with all fixing accessories and lamp as reqd.				

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
a	36 watt recess mounting LED light fixture 600 X 600 mm Maske crompton or tis equivalent.	6.00	Nos.		
33	S & F testing & commissioning of venture cool white 150 W sodium metal halide as reqd.	10.00	Nos.		
	Total Rs.				