

## QUOTATION

Sub:- Replacement and rerouting of submain wires from floor panel to DB of Lab No. 204 at new core labs.

S No.	DESCRIPTION	QTY	UNIT	RATE (Rs)	AMOUNT
				Words & Fig.	
1	Supplying of one no. 3.5 x 35.0 sqmm PVC insulated, XLPE steel armoured aluminium conductor power cable of grade 1.1 kV as required complete in following manners.	90.00	Mtr.		
2	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.				
a	Upto 35 sq. mm (clamped with 1mm thick saddle)	10.00	Mtr.		
3	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.				
a	Upto 35 sq. mm (clamped with 1mm thick saddle)	80.00	Mtr.		
4	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	2.00	Mtr.		
5	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	85 mm flexible cover	2.00	Mtr.		
b	End cap	4.00	Nos.		
6	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				

S No.	DESCRIPTION	QTY	UNIT	RATE (Rs)	AMOUNT
-------	-------------	-----	------	-----------	--------

Words & Fig.

a	3½ X 35 sq. mm (32mm)	2.00	No.		
---	-----------------------	------	-----	--	--

7 Supplying and installing following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required.

a	300 mm width X 50 mm depth X 1.6 mm thickness	30.00	Mtr.		
---	---	-------	------	--	--

**Total Rs.**



अधिकाारी अभियंता (वि०) E.E. (Elect.  
संनिवि०, मा०प्रौ० संस्थान, कानपुर  
I W.D., I.L.L. Kanpur

