QUOTATION

Sub Repairing/replacement of defective electrical items in FB 626, Biomaterial Lab, TB 101 AND 112, FB 670 and different labs and offices in academic area on complaint basis.

		Qty	UNIT	RATE	AMOUNT
			~	(In words & Figures)	_ =526
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as required.				
a	3 x 2.5 sq. mm	11.00	Metre		
b	3 x 4 sq. mm	7.00	Metre		
c	3 x 10 sq.mm.	30.00	Meter		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	5.00	No.		
b	15/16 A switch	5.00	No.		
c	3 pin 5/6 A socket outlet	4.00	No.		
d	6 pin 15/16 A socket outlet	4.00	No.		
	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a (6 Module	3.00	No.		
f	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.			9	
a S	Single pole 5 A to 32 A	1.00	No.		

SL No	DESCRIPTION	Qty	UNIT	RATE (In words & Figures)	AMOUNT
b	Double Pole (40A-63A)	1.00	Nos.		
c	Triple pole (40A-63A)	1.00	Nos.		
d	Four Pole (40A-63A)	1.00	Nos.		
5.00	Supply and fixing of 32 x 20 mm DLP minitrunking white-system with independent cover etc. as required complete.		Meter		
6.00	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	4.00	Nos.		
7.00	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	22.00	Nos.		
8.00	Dismantling and refixing of M.S./PVC box of up to 250 x 300 x100 on surface recessed as required. including painting with enamel paint as reqd	1.00	Nos.		
9.00	Providing connection for motor/ panel starter/ transformer upto 1 Kva / steblizer.	1.00	Nos.		
10.00	Supplying and fixing following size/modules, plastic box for modular switches in recess etc as required.				
a	6 Module	3.00	Nos.		
11.00	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	3.00	Nos.		
12.00	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.			ā	
a	20 watt ESENTIAL PHILIPS or equivalent Tube inplace of 36/40 W FL tube	28.00	Nos.		
b	18 watt. LED PLL lamp	1.00	Nos.		

SL No.	DESCRIPTION	Qty	UNIT
13.00	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.		<i>p</i> =
a	2 X 20W Box type LED tube with fitting	2.00	Nos.
b	12 watt resess mounting LED light fixture	6.00	Nos.
C	18 watt recess 300 x 300 mm mounting LED light fixture	1.00	Nos.
d	36 watt recess mounting LED light fixture 600 x 600 mm	13.00	Nos.
e	36 watt recess mounting LED light fixture 300 x 1200 mm	2.00	Nos.
	Supply and fixing testing and commissioning of 1X10 watt LED mirror light fixture with Electronic driver, lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.(eq. To Cropmton cat. no.LCTLN-10-CDL). Total Rs.	1.00	Nos.

कार्यकारी डोगमना (वि)/E.E.(Elect.) स्थानिकवित, मांव प्रोच सरकान, कानपुर I.W.D., L.I.T. Kampur

AMOUNT

RATE (In words & Figures)