QUOTATION

Sub Repairing & replacement of defective switch/ socket, casing & capping, Distribution boards, LED fitting etc. At Computer centre, KD- 222 lab, KD- 111, IME-305, NL-2-104, JEE/ Gate building 209, 211, Telephone exchange, NL-2- 101 Northern lab-1 and other north side drive residences as per enclosed complaints at IIT Kanpur

S.N	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit as required.				
1.1	3 x 1.5 sq. mm	30.00	Metre		
1.2	3 x 2.5 sq. mm	58.00	Metre		
1.3	3 x 4 sq. mm	9.00	Metre		
2	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
2.1	25 mm	10.00	Metre		
3	Supply and fixing of 32 x 20 mm DLP minitrunking white-system with independent cover etc. as required complete.	26.00	Meter		
4	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
4.1	internal / external angle	10.00	Nos.		
4.2	changeable flat angle	7.00	Nos.		
4.3	flat junction	1.00	Nos.		
5	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required	34.1			
5.1	20 mm	5.00	Meter		

S.f	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
6	Supply and Galacter C.C. H.			(In words & Figures)	
0	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.			: 25m	
6.1	2 X 20W Box type LED tube with fitting	2.00	Nos.		
6,2	12 watt resess mounting LED light fixture	2.00			
(2	10		Nos.		
6.3	18 watt recess 300 x 300 mm mounting LED light fixture	2.00	Nos.		
6.4	36 watt recess mounting LED light fixture 600 x 600 mm	4.00	Nos.		
7	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
7.1	20 watt ESENTIAL PHILIPS or equivalent Tube inplace of 36/40 W FL tube	5.00	Nos.		
8	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
8.1	3 Module	4.00	Nos.		
8.2	6 Module	7.00	Nos.		
8.3	12 Module	3.00			
9	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.		Nos.		
9.1	3 Module	4.00	No.		
9.2	6 Module	7.00	No.		
9.3	12 Module	3.00	No.		

S.N	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
10				(În words & Figures)	
10	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
10.1	5/6 A switch	25.00	No.	150	
10.2	15/16 A switch	10.00	No.		
10.3	3 pin 5/6 A socket outlet	10.00	No.		
10.4	6 pin 15/16 A socket outlet	10.00	No.		
10.5	Fan regulator two module stepped type	7.00	No.		
10.6	Blanking Plate	1.00	No.		
11	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	2.00	Nos.		
12	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
12.1	Double pole 5 A to 32 A	2.00	No.		
13	Supplying and fixing connecting and commissioning of AC 230/250 volts, 50 HZ, 250 mm sweep fresh air fan including providing nuts, bolts, mounting frame and other accessories etc. complete	1.00	Nos.		
	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required.	2.00	Each		

S.N	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
15	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	42.00	Nos.		
16	Dismantling concealed & damaged DB/TPN Switches/starter/ loose wire boxes along with all accessories and depositing the same in the sectional store repairing the damages as reqd complete.	3.00	Nos.	ets-	

Total Rs.

স্থিতমন্ত্ৰ কৰিবলা (দিন) / ह ह (हिन्छः) স্বাহনিক হৈ, আন এটা মঞ্চনল ক্ষানুস্থ 1, W. Fr., L.T., Karer