


QUOTATION

Name of work:- Providing connectivity between main busbar to MCCB in LT panel of Substation No. 8.

S.No.	Description of item	Qty	Unit	Rate (In words & figures)	Amount
1	Supplying and drawing of following sizes of FR PVC insulated unarmoured copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	240sqmm	13.00	Mtr		
2	S/F, copper cable lug suitable for following size of conductor.				
a	240sqmm	12.00	Each		
3	Supplying, connecting and commissioning of 1x50x10mm aluminium bus bar including bending to suitable shape, making hole for nut-bolts, providing and fixing bus bar insulators, slivering, nut-bolts in existing panel/box for connections etc. as required complete.	5.00	Mtr		

Total Rs.


अधीक्षक अभियन्ता / S.E.
सोनिकवि (I.W.D.)
भाउप्री संस्थान, काठमाडौं
I.I.T., Ka
