

QUOTATION

Name of work:- Replacement of damaged underground LAN Wire House N0-401 Type-IV and Lay 3 uplink wire from Earth science building to Geo Tech building as per requested by computer centre in the campus.

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	410.00	Mtr.		
2	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	1.00	Nos.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	10.00	Mtr.		
b)	25 x 16 mm	10.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 32 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	289.00	Mtr.		
b)	In pipe	13.00	Mtr.		
c)	In open duct	1.00	Mtr.		
d)	On surface with MS clamp	1.00	Mtr.		

6

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
5	S & F metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in the front I/c painting etc as reqd.				
a)	200 mm x 150 mm x 60 mm deep	2.00	Nos.		
6	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	50 mm	13.00	Mtr.		
7	Supplying, installation DLP mini-trunking 32mm x 20mm and accessories white-system with independent cover-without central partion etc. as reqd.				
7.1	Mini- trunking	10.00	Mtr.		
7.2	End cap left or right	2.00	Nos.		
7.3	Internal/ external angle	1.00	Nos.		
7.4	Flat angle	2.00	Nos.		
7.5	Flat junction	1.00	Nos.		

Total Rs.

[Handwritten Signature]

अधीक्षक अभियन्ता / S.E.
संविधिक (I.W.D.)
भा.प्रौ. संस्थान, कानपुर
I.I.T., Kanpur
[Handwritten Signature]