


QUOTATION

Name of work:- Required 05 pair Jelly filled cable from DP Near House No.606 to H.No.608.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	S&L, connecting and commissioning following 5 pairs jelly filled armoured telephone cable PVC insulated and PVC sheathed annealed tinned copper conductor.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	80.00	Mtr.		
b)	In pipe	5.00	Mtr.		
c)	In open duct	5.00	Mtr.		
d)	On surface with MS clamp	5.00	Mtr.		
2	Fixing Telephone DB loose wire boxes along with all accessories as reqd.	1.00	Nos.		
3	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	50 mm	5.00	Mtr.		

Total Rs.




अधीकृत अभियन्ता / ए.ई.
सोनिओविओ (I.W.D.)
माओप्रौओ सस्थान, कानपुर
I.I.T., Kanpur
