


QUOTATION

Name of Work: Required New wiring at 22 different rooms of health centre with RJ-11 Point.

S.No.	Description	Quantity	Unit	Estimated rate without GST	Estimated Amount without GST
1	Supplying and drawing 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.	450.00	Metre	33.32	14993.42
2	RJ 11 Telephone socket	22.00	Nos.	210.43	4629.55
3	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
3.01	1 or 2 Module	22.00	No.	304.25	6693.56
4	Supply and fixing of 32 x 12.5 mm DLP mini-trunking white-system with independent cover etc. as required complete.	300.00	Meter	178.87	53660.68
5	Supply and fixing of following accessories suitable for 32 mm x 12.5 mm size plastic trunking white system.				
5.01	End cap	25.00	Nos.	82.42	2060.50
5.02	internal / external angle	60.00	Nos.	107.85	6470.85
5.03	changeable flat angle	15.00	Nos.	118.37	1775.54
5.04	flat junction	20.00	Nos.	151.69	3033.76
Total Rs.					93317.84
Estimated Amount Rs.					93318.00
Please quote percentage above/below(%) =					


विनय कुमार तिवारी
(VINAY KUMAR TIWARI)
अभिषेकी अभिवंता (वि) इ.इ. (Elect.)
०६०००६, भा० प्र० संस्थान, कांगूर
W.D., I.I.T., Kangur
