

QUOTATION

Name of work :- Locating, rectifying removing faults in the power cable feeding DG power supply from DG room to lifts of Hall-13 with allied works as required in the campus as per complaint attached herewith.

S.No	DESCRIPTION	Qty	Unit	Rate	Amount
(In words & Figures)					
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
a)	Above 95 sq. mm and upto 185 sq. mm	20.00	Metre		
2	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a)	3½ X 120 Sq. mm	2.00	Nos.		
3	Supplying of one no. XLPE sheathed aluminum conductor steel armoured power cable of size 3½ X 120 sq.mm. 1.1kV grade.	20.00	Metre		
4	Locating fault of by using fault locating machine for cable (HT/LT cable) in the cable lines meggaring etc and rectifying removing & restoring the same and making good the damages cable etc as directed by the Engineer Incharge.	1.00	Nos.		

S.No	DESCRIPTION	Qty	Unit	Rate	Amount
------	-------------	-----	------	------	--------

(In words & Figures)

5 Lifting removing cable of following size from trench/clamps, making roll & depositing the same in store I/c cartage.

a) above to 95 upto 185 Sq.mm. 10.00 Metre

6 Digging trench for taking out cable upto 400 Sq.mm. and refilling , watering ,ramming the same after taking out cable as reqd complete. 10.00 Metre

Total Rs.

[Handwritten Signature]

अधीक्षक अभियन्ता/S.E.
सोनिओविड (I.W.D.)
भाओप्रौओ सस्थान, कानपुर
I.I.T., Kanpur

[Handwritten Signature]

[Handwritten Signature]