

QUOTATION

Name of work:- Replacement of damaged underground LAN Wire House N0-436 Type-IV as per requested by computer centre in the campus.

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
2	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
2.1	20 x 12 mm	10.00	Mtr.		
2.2	25 x 16 mm	10.00	Mtr.		
3	Supply and laying of HDPE pipe ISI mark of 32 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
3.1	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	65.00	Mtr.		
3.2	In open duct	1.00	Mtr.		
3.3	On surface with MS clamp	1.00	Mtr.		
4	S & F metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in the front I/c painting etc as reqd.				
4.1	200 mm x 150 mm x 60 mm deep	1.00	Nos.		

2

S.No.	Description	Qty.	Unit	Rate	Amount
-------	-------------	------	------	------	--------

(In words & Figures)

5	Supplying and drawing of UTP 4 pair CAT 6 LAN Cable in the existing surface/ recessed Steel/ PVC conduit as required.				
5.1	1 run of cable	140.00	Mtr.		

Total Rs.

7
 अधीक्षक अभियन्ता / S.E.
 सॉफ्टवेयर (I.W.D.)
 भास्कर संस्थान, कानपुर
 I.I.T., Kanpur

[Handwritten signature]