

INDIAN INSTITUTE OF TECHNOLOGY, KANPUR
Institute works Department, Division – II

Name of Work :- Providing and fixing of Signage for Shivani Centre

S. No.	Description of Item	Unit	QTY	Rate	Amount
	Minor Civil Maintenance work				
1.	Supply and fixing of Signage Fabrication of 3 mm Aluminum Composite panel (ACP) exterior grade sheet with a retro reflective type IV grade media of 3 M brand in double layer sticking on the ACP sheet as per approved design i/c necessary SS screws etc. All complete as per direction of Engineer-in-charge.	Sqm	3.35		
2.	Providing and fixing in position 304 grade stainless steel frame fabrication of stainless square and round tube of specified size and design fixed to vertical stainless steel round tubes of specified diameter and length for installation of signage board complete as per approved design & direction of Engineer-in-charge. The rate is excluding of excavation and concrete.	Kg	100		
		Total			
		GST@			
		Grand Total in Rs			



(R.K. Verma)

Acting Superintending Engineer

